


South32 - Illawarra Metallurgical Coal

DENDROBIUM MINE

End of Panel Groundwater Assessment for Longwall 18
(Area 3B)



HGEO Pty Ltd

Date: September 2022

Project number: J21543

Report: D22191

DOCUMENT REGISTER

Revision	Description	Date	Comments
01	1 st Draft	30/8/2022	IMC revision
02	Final	15/9/2022	pdf

FILE

https://hgeocomau.sharepoint.com/sites/HGEO/Shared Documents/Files/Client_Site/Dendrobium/04_Projects/03_EOP_Reports/J21543_EOP_LW18_Groundwater/D22191_S32_EOP_LW18_Groundwater_V03.docx

QUALITY CONTROL

Process	Staff	Signature	Date
Authors	Stuart Brown		
Approved	Stuart Brown		15/9/2022

COPYRIGHT

© HGEO Pty Ltd 2022

Copyright in the drawings, information and data recorded in this document (the information) is the property of HGEO Pty Ltd. This document and the information are solely for the use of the authorised recipient and this document may not be used, copied or reproduced in whole or part for any purpose other than that for which it was supplied by HGEO Pty Ltd. HGEO Pty Ltd makes no representation, undertakes no duty and accepts no responsibility to any third party who may use or rely upon this document or the information.

TABLE OF CONTENTS

1. INTRODUCTION	6
1.1 Longwall 18.....	7
1.2 WaterNSW feedback on previous EOP report	7
1.3 Hydrogeology.....	7
1.4 Effects of mining	9
1.5 Numerical groundwater impact model.....	10
2. MONITORING DATA.....	11
2.1 Management Plan	11
2.2 Groundwater monitoring network	11
2.3 Deep groundwater levels.....	11
2.4 Mine water balance	13
2.5 Groundwater chemistry	13
3. ASSESSMENT OF GROUNDWATER RESPONSE TO MINING	15
3.1 Mine water balance	15
3.2 Deep groundwater levels – time-series hydrographs.....	20
3.3 Deep groundwater levels – spatial patterns	28
3.4 Comparison with model predictions	33
3.5 Groundwater chemistry	35
4. CONCLUSION	38
5. REFERENCES	39
APPENDIX A: List of monitoring bores	41
APPENDIX B: Groundwater hydrographs.....	44

LIST OF TABLES

Table 1. WaterNSW groundwater recommendations from previous EOP report.....	7
Table 3. Dendrobium Mine Inflow during the Extraction of Longwall 17 (in ML/day).....	15
Table 6. Summary of EC measurements at monitoring bores	37

LIST OF FIGURES

Figure 1. Location of Dendrobium Mine and surface geology.....	6
--	---

Figure 2. Generalised stratigraphy of the Southern Coalfield	8
Figure 3. Geological cross-section (east-west) through Dendrobium Mine	10
Figure 4. Deep groundwater monitoring network around Areas 2, 3A and 3B	12
Figure 5. Strip plot showing the range in EC of surface water, groundwater and mine inflow	14
Figure 6. Groundwater inflow from water balance for all mine areas (ML/day)	16
Figure 7. Groundwater inflow to the mine for Areas 3A and 3B (ML/d)	16
Figure 8. Estimate of potential surface water component to Area 3B water balance	17
Figure 9. Tritium concentration in water samples from Area 3B	18
Figure 10. Timeseries of % modern carbon in mine water samples	19
Figure 11. Modelled versus observed piezometric head for Avon Dam monitoring sites	23
Figure 12. Cross sections of Elouera fault showing investigation holes	25
Figure 13. Groundwater hydrograph for Elouera fault monitoring bore S2441B (Site 1).....	27
Figure 14. Groundwater hydrograph for Elouera fault monitoring bore S2465 (Site 2)	27
Figure 15. Groundwater hydrograph for Elouera fault monitoring bore S2490 (Site 3)	28
Figure 16. Sensors recording desaturated conditions in the Hawkesbury Sandstone (2022)	30
Figure 17. Drawdown in piezometric head in the lower Hawkesbury Sandstone (2009-2022)	30
Figure 18. Piezometric head in the lower Hawkesbury Sandstone relative to Lake Avon (2022)	31
Figure 19. Drawdown in piezometric head in the upper Bulgo Sandstone (2009-2022)	31
Figure 20. Drawdown in piezometric head in the lower Bulgo Sandstone (2009-2022).....	32
Figure 21. Drawdown in piezometric head in the Scarborough Sandstone (2009-2022)	32
Figure 22. Observed versus model predicted heads at the end of Longwall 18	33
Figure 23. Observed versus model predicted mine groundwater inflow to mine Area 3B	34
Figure 24. Map showing the layout of the local-scale numerical model (colour shading represents variation in hydraulic conductivity).....	35
Figure 25. Time series of groundwater EC and pH at S2314_75m (AD2).....	36
Figure 26. Time series of tritium and percent modern carbon (pMC) at S2314_75m (AD2) ..	36

EXECUTIVE SUMMARY

This report provides an assessment of the hydrogeological effects of Longwall 18 extraction in Area 3B at Dendrobium Mine, as required under the conditions of mining approval. Extraction of Longwall 18 commenced on 2/12/2021 and was completed on 17/5/2022. Longwall 18 is the tenth panel to be extracted in Area 3B, with an extracted length of 1018 m, a void width of 305 m (including first workings) and a cutting height of up to 3.9 m.

The average daily inflow to Area 3B during Longwall 18 extraction was 4.5 ML/day and total mine inflow was 9.1 ML/day. Pumping of water from Area 3B decreased by 14% compared with the previous longwall, despite an increase in total mine inflow in response to record rainfall over the past year. The apparent decline in Area 3B inflow is due to a pause in pumping from the area in March-April 2022. Isotopic tracers of modern water (tritium and 14C) continue to indicate negligible or minor components of modern water in water pumped from Area 3B.

Groundwater salinity (as indicated by Electrical Conductivity – EC) shows a general increase with depth below the surface. Declining EC was reported in two monitoring bores located adjacent to Lake Avon (S2314_75m and S2436_35m) following Longwall 17. A review of water chemistry and isotopic data following Longwall 18 finds that the trend is not continuing. There is no adverse trend in isotopic indicators of groundwater age (14C and Tritium).

Mining of Longwall 18 resulted in continued depressurisation of the target coal seam and overlying strata in general agreement with numerical model predictions. Importantly, for piezometers installed in the barrier zone between Lake Avon and Area 3B, observed groundwater drawdown is generally less than predicted. As expected, the greatest depressurisation is within the Wongawilli Coal Seam and deeper strata, and decreases with height above the seam.

Piezometers installed after longwall extraction indicate significant depressurisation throughout all strata and throughout the Hawkesbury Sandstone (HBSS) in most holes. Holes drilled above extracted longwalls provide evidence for groundwater perching and recovery in the years following mining. Drawdown in the HBSS reduces with distance and is typically negligible at distances greater than 1.2 km from the goaf footprint.

Piezometers installed along the barrier zone between Lake Avon and extracted longwalls in Area 3B show declines in piezometric heads to levels below contemporaneous water levels in Lake Avon and changed in strata permeability due to mine subsidence. Seepage losses from Lake Avon have been estimated by regional and local scale numerical models to be in the range 0.09 to 0.89 ML/day as at the end of Longwall 18. The estimates are within the tolerable loss limit of 1 ML/day prescribed by Dams Safety NSW and supported by the low levels of tritium and 14C in mine inflow water in Area 3B.

The Elouera Fault is located to the south of Area 3B, between Longwall 18 and Elouera Mine Longwall 8. IMC carried out a detailed hydrogeological investigation of the fault prior to Longwall 18 which concluded that the fault was unlikely to form a conduit to flow. Subsequent monitoring confirms this to be the case. No anomalous inflow was associated with structures intersected during Longwall 18 extraction. TDR monitoring shows no evidence for movement on the fault plan during or after Longwall 18. Piezometers installed within and across the fault show no anomalous drawdown within the fault core, indicating that the fault is not anomalously conductive along the fault plane.

I. INTRODUCTION

Illawarra Metallurgical Coal (IMC) operates the Dendrobium underground coal mine, located approximately 12 km west of Wollongong (NSW) in the Southern Coalfield (Figure 1). IMC is required under the conditions of mining approval to submit regular reviews of the local hydrological data, including groundwater level and quality, and potential seepage losses from stored water.

IMC operates an extensive network of groundwater monitoring sensors (piezometers), groundwater sampling pumps and down-hole geotechnical instruments. Groundwater data from more than 950 active piezometers at 181 monitoring bores is updated monthly via telemetry or collected by IMC field teams.

This End of Panel (EoP) assessment reviews groundwater level and quality monitoring data up to one month after the completion of Longwall 18 (cumulative). Data are assessed against baseline and impact criteria defined in the Trigger Action Response Plan (TARP) which forms part of the Subsidence Management Plan for Area 3B (BHPBilliton, 2015) and the Groundwater management plans contained therein.




Figure 1. Location of Dendrobium Mine and surface geology

1.1 Longwall 18

Longwall mining at Dendrobium has been carried out in three designated areas: Area 1 (east of Lake Cordeaux), Area 2 (west of Lake Cordeaux), and Areas 3A and 3B (between Lake Cordeaux and Lake Avon). Coal is extracted from the Wongawilli Seam in Areas 1 through 3B. Previous workings in the Wongawilli Seam are located to the south at Elouera and Nebo, and to the east at Kemira. The overlying Bulli Seam was mined previously at Mt Kembla to the east of and partially overlapping Area 1.

Extraction of Longwall 18 commenced on 2/12/2021 and was completed on 17/5/2022. Longwall 18 is the tenth panel to be extracted in Area 3B, with an extracted length of 1018 m, a void width of 305 m (including first workings) and a cutting height of up to 3.9 m.

1.2 WaterNSW feedback on previous EOP report

WaterNSW reviewed the Longwall 17 End of Panel reports and provided comments to the NSW Department of Planning Industry and Environment in a letter dated 11/5/2022. WaterNSW provided the following recommendations in relation to groundwater (Table 1):

Table 1. WaterNSW groundwater recommendations from previous EOP report

Recommendation	Response
<p><i>Implement HGEO recommendations to increase analysis and sampling frequency (to quarterly) at AD2. If data permit, clarify relationship between postmining changes in hydraulic conductivity, groundwater recovery and water quality results</i></p>	<p>Water quality results at AD2 are reviewed in Section 3.5. Tritium and Carbon-14 analysis indicates no significant change in groundwater age at AD2. Increasing EC trend no longer apparent. Recommendation: Resume annual water quality sampling and analysis for AD2 and other AD-series monitoring bores.</p>

1.3 Hydrogeology

Dendrobium Mine is located within the Southern Coalfield which is one of the five major coalfields that lie within the Sydney Geological Basin. The stratigraphy of the Southern Sydney Basin is shown in Figure 2. The Basin is primarily a Permo-Triassic sedimentary rock sequence, underlain by undifferentiated sediments of Carboniferous and Devonian age. The Bulli and Wongawilli Coal Seams are the primary target seams in the top part of the Illawarra Coal Measures. The Coal Measures are overlain by Triassic sandstones, siltstones and claystones of the Narrabeen Group and the Hawkesbury Sandstone (HBSS). The HBSS is the dominant outcropping formation across the mine area, but lower stratigraphic units (Bald Hill Claystone (BHCS), Narrabeen Group) are exposed in deeply incised parts of Wongawilli Creek and along the south-eastern shores of Lake Cordeaux.

The hydrogeology of the area is described in previous groundwater assessments associated with Dendrobium Mine (e.g. Coffey, 2012; HydroSimulations, 2016; Parsons Brinckerhoff, 2014), and summarised below.

Three main groundwater systems are recognised:

1. Perched groundwater systems associated with swamps and shallow sandstone. These may be ephemeral and/or disconnected from the deeper groundwater systems;
2. Shallow groundwater systems: layered water-bearing zones within the saturated HBSS; and
3. Deeper groundwater systems within the Narrabeen Group and the Illawarra Coal Measures.

Recharge to the aquifer systems is primarily from rainfall infiltration through outcropping formations, generally the HBSS in the western half of the Dendrobium mine area and the Bulgo Sandstone (BGSS) in the eastern half. There will be some recharge from the Reservoirs and streams to host formations at times of high-water level and creek flooding.

Strong topographic relief and recharge drive vertical groundwater flow near the ground surface, but at depth the alternation of aquifers and aquitards promotes horizontal groundwater flow at the base of permeable units. In general, groundwater flow in shallow systems is strongly influenced by local topographical features such as streams and lakes, whereas deeper groundwater systems are influenced by regional topographic and drainage patterns (Toth, 2009). Regional groundwater flow in the deeper sandstone units (pre-development) is predominantly northwest, towards the Nepean River system and away from the Illawarra escarpment.

Discharge from the (shallow) groundwater systems occurs naturally at the surface to creeks and to the reservoir as baseflow and seeps, and by evapotranspiration through vegetation. Along the escarpment to the south-east of Dendrobium Mine, groundwater discharge appears as seeps in cliff faces at the junction of formations with contrasting permeability.




Figure 2. Generalised stratigraphy of the Southern Coalfield

1.4 Effects of mining

Extraction of coal using longwall methods commonly results in ground subsidence and associated deformation and fracturing of overlying strata (Peng and Chiang, 1984; Whittaker and Reddish, 1989). Fracturing is most intense and vertically connected immediately above the collapsed longwall (goaf), and grades upwards through zones of less fractured strata (Booth, 2002). Fracturing of the overburden can cause significant changes in aquifer characteristics such as permeability and storage, and potentially can provide pathways for vertical groundwater movement between shallow groundwater and surface water systems and underground mines (Advisian, 2016; McNally and Evans, 2007). The height to which vertically connected (and free-draining) fracture networks extend above the mined seam is therefore important in assessing potential impacts of longwall mining on groundwater and surface water systems.

Several authors have developed empirical approaches to estimating the height of connected fracturing or complete groundwater drainage above longwalls; for example, Forster 1995; Guo *et al.* 2007; Mills 2011; Tammetta 2013; Ditton & Merrick 2014. These methods have been used at numerous coal mines in NSW to provide guidance on the height of fracturing (or depressurisation) for the development of numerical groundwater impact models. It is important to note that the terms used by the authors are not equivalent; Tammetta refers to the “height of desaturation” (more precisely, complete depressurisation); Ditton and Merrick refer to a “zone of continuous cracking” (Zone A), and Mills refers to a zone of large downward movement (Zone 2).

The Independent Expert Panel for Mining in the Catchment (IEPMC) was established in 2018 to provide advice to government on impacts of mining activities in the Greater Sydney Water Catchment Special Areas, with a focus on risks to quantity of water (IEPMC, 2019a, 2019b). In relation to hydrogeological impacts and height of fracturing, the Panel considers that:

“...changes in ground behaviour and fracturing, permeability and the lateral extent of affected areas occur gradationally rather than as step changes. The so-called ‘fractured zone’ is a misnomer. Fracturing still develops above this zone and may be connected. Due largely to the different interests and focus of geoscience and engineering disciplines, zones defining mining-induced rock deformation do not necessarily align with zones defining groundwater response to mining.”

Adhikary *et al.* (2020) reviewed strata-caving mechanics and the observations of Tammetta (2013) and developed empirical equations defining upper and lower bound estimates for the height of connected fracturing. The equations are functions of the effective panel width (W') and height of mining (t) only. The authors propose that the upper and lower bounds could be used to define possible ranges of fracturing heights in probabilistic modelling, and that the upper bound should be used as a conservative assumption in deterministic studies¹. Modelling indicated that subsidence above wide or super-critical² panels would be accommodated by fracturing to the surface; however, the authors emphasise that the seam to surface fracturing does not imply seam to surface connection. In addition, rock mass dilation may result in sudden and complete piezometric pressure drops throughout overlying strata that are independent of (and beyond) the connected fracture network. Initial piezometric pressure loss may recover to various degrees depending on the fracture network, recharge rate, and aquitard integrity including the presence of self-healing clay-rich aquitards. Those conclusions are consistent with observations at Dendrobium as summarised in this report.

¹ Note that for Area 3B, the lower and upper bounds of Adhikary *et al.* (2020) are 199 – 387 m. Those values bracket or contain estimates based on Mills 2011 (305 m), Tammetta 2013 (351 – 377 m) and Ditton & Merrick 2014 (216 – 258 m; Geol-A95).

² Adhikary *et al.* (2020) define critical and super-critical width, in the absence of site-specific data, as $W/d \geq 1.2$ and ≥ 1.4 , where W is the effective panel width and d is the depth of cover (seam top to ground surface). For longwalls in Area 3B W/d ranges from 0.74 to 1.12 (sub-critical).

Since 2018 IMC has carried out targeted investigations into the height of fracturing and groundwater conditions above completed longwalls at Dendrobium Mine. Investigation holes have been drilled above existing Longwalls 12 to 18 in Area 3B and Longwalls 6 and 7 in Area 3A, allowing assessment of effects above longwalls of different width. The main findings of the investigation are summarised in Section 3.2.1.

1.5 Numerical groundwater impact model

Regional numerical modelling by Coffey (Coffey, 2012) supported the *Area 3B Subsidence Management Plan* (SMP) application and subsequent approval. The model has been revised and updated several times since 2012 to better represent subsidence fracturing and to allow assessment of shallow groundwater within swamps and baseflow to streams (HydroSimulations, 2016). The current model was developed by Watershed Hydrogeo (2020) using MODFLOW-USG. The model includes historical mining at Dendrobium and surrounding mines.

The vertical extent of layers used to simulate the regional groundwater systems in the latest numerical model are shown in Figure 2. An East-West cross section showing the modelled stratigraphy is presented in Figure 3.




Figure 3. Geological cross-section (east-west) through Dendrobium Mine

2. MONITORING DATA

This section presents the monitoring data available for the groundwater assessment and supports the discussion of the observed hydrological behaviour presented in Section 3.

2.1 Management Plan

Groundwater monitoring at Dendrobium Mine is conducted in accordance with the “Dendrobium Colliery Area 3B SMP Groundwater Management Plan” (South32, 2012) and the Area 3B Subsidence Management Plan (BHP Billiton, 2015). The aims of the Groundwater Management Plan are to:

- Monitor groundwater levels and quality, commencing at least one year prior to mining affecting the system;
- Project potential groundwater changes during mining (short term) and post-mining (long term) with particular attention to the effect of changes to groundwater regime, impact on the catchment yield and interaction with the stored waters;
- Identify hydraulic characteristics of overlying and intercepted groundwater systems, and determine changes to groundwater systems due to coal extraction and dewatering operations;
- Report any pumping tests and groundwater/surface water simulation studies; and
- Collect water level data from relevant groundwater-monitoring locations.

2.2 Groundwater monitoring network

The groundwater-monitoring locations for Areas 3B are shown in Figure 4. A list of all monitoring bores installed at Dendrobium is included in Appendix A. There are approximately 181 active monitoring bores located across the Dendrobium mine lease, containing over 950 piezometers, excluding those that are decommissioned or no longer monitored.

2.3 Deep groundwater levels

Deep groundwater levels are monitored using one or more piezometers installed within monitoring bores. Monitoring bores typically have an index number with an ‘S’ prefix such as S2314, within which piezometers may be installed at multiple depth levels (e.g. S2314_128m). In most cases, the piezometers are vibrating wire piezometers (VWP) that are fully grouted into the bore hole. The sensors contain a sensitive diaphragm that deforms in response to subtle changes in pore pressure that are transmitted through the connected pores of the grout from the adjacent geological strata. VWP sensors are commonly used in deep mining and geotechnical applications where the strata permeability is low and conventional (standpipe) piezometers are impractical (Contreras et al., 2008; Mikkelsen and Green, 2003).

Standpipe piezometers, consisting of a slotted open casing, are best suited to monitoring of relatively shallow groundwater systems within moderate to high permeability strata (e.g. swamp sediments and shallow HBSS). Automated loggers record groundwater pressures each hour (typically). The recorded data are subsequently converted to fluid pressure head (m) and potentiometric head (mAHD).

Deep groundwater responses to mining are assessed primarily through the use of time-series hydrographs for multi-level piezometer sites (VWPs). Most VWPs at Dendrobium suffer from electromagnetic noise which causes spurious spikes in the data records. Noisy data are filtered and removed where practical. Hydrographs and analysis are presented in Section 3.1.




Figure 4. Deep groundwater monitoring network around Areas 2, 3A and 3B

Hydrographs are plotted in terms of **piezometric head** (mAHD) and **pressure head** (m H₂O). Piezometric head can be thought of as the theoretical level to which water would rise in a bore that is open to an aquifer at a given elevation and is calculated by adding the measured pore pressure (at the VWP, expressed in m of water) to the elevation of the sensor (in m AHD). The potentiometric head in a confined aquifer system can be (and often is) different to the water table elevation at the same location.

Hydrographs presented in this assessment include surface water hydrographs for the nearest water supply reservoir (Lake Cordeaux for Area 3A and Lake Avon for Area 3B hydrographs). Note also that individual hydrograph traces are presented as dotted lines at times when the pressure head is below a threshold of 2 m. The **pressure head** is the absolute pore pressure at the sensor expressed in m of water. When the pressure head is below that threshold it is an indication that the rock matrix is approaching complete depressurisation at the location of the sensor and, given the uncertainty in pressure measurements, may be totally or partially desaturated. Both piezometric and pressure head hydrographs are presented in Appendix B.

Assessment of the spatial distribution of piezometric head and pressure drawdown over the reporting period is carried out using annotated and coloured symbols on a map. **Drawdown** (in metres) is simply the difference in potentiometric head between a reference date and the end of the current reporting period.

In this assessment the groundwater drawdown reference date is November 2009, immediately prior to the start of mining at Area 3A. This date was selected because very few piezometers were operational in Area 3B prior to 2009. The following procedure was used to calculate groundwater drawdown.

- Piezometric head and pressure head data were tabulated from the Dendrobium VWP database. Data were reduced to daily observations using a median of sub-daily data.
- The median head at each operational sensor was obtained for the last 3 months of the recently completed longwall and the last three months of Longwall 5 (ending in November 2009). This approach is used to capture sensors with records that fall slightly short of the end of panel.
- The average head was calculated for each of five subunits: middle HBSS, lower HBSS, upper BGSS, lower BGSS and SBSS. This allows piezometric heads to be compared at bore locations where sensors are set at inconsistent depths. The subunits also correspond to the subunits used in the regional numerical model, allowing direct comparison with model predictions.
- For bores that were installed after 2009, the piezometric head in 2009 was spatially interpolated from sensors within each subunit that were active at that time (using kriging).
- Drawdown was calculated for each subunit as the difference between median heads at the end of the recently completed longwall and the end of Longwall 5 (either observed or interpolated).
- Where one or more of the sensors in the subunit recorded less than 1 m of pressure head (assumed to be near desaturation), the drawdown is recorded as a minimum. Those locations are highlighted on the relevant spatial plots.
- Sensor data for decommissioned or damaged bores are not extrapolated. Locations that have been decommissioned, damaged or for which data are otherwise unavailable at the time of reporting are not included in analysis.

Spatial plots are presented and discussed in Section 3.3.

2.4 Mine water balance

All movements of water via pumping stations is monitored and controlled in real-time through the System Control and Data Acquisition (SCADA) system and used to calculate a daily mine Water Balance. The Water Balance is an accurate measure of all water that enters, circulates and leaves the mine, including via air moisture and coal moisture content. Mine water seepage (groundwater inflow), which cannot be directly measured, is determined by mass balance for each goaf and is therefore known to a reasonable accuracy. Key metrics of the Mine Water Balance are reported against Trigger Action Response Plan (TARP) levels to Dams Safety NSW monthly.

In this assessment, the estimated groundwater inflow component of the mass balance is presented as time-series hydrographs and compared with rainfall trends and model predictions. Analysis of water balance trends for the reporting period is presented in Section 3.

2.5 Groundwater chemistry

Groundwater chemistry sampling sites relevant to this assessment are shown in Figure 4 (blue symbols). Currently there are eight sampling bores in Area 3B containing 20 individual sampling pumps screened within the Hawkesbury and Balgo Sandstone. Most sampling sites are located between the mined and planned longwalls of Area 3B and the eastern shore of Lake Avon. The SBSS is monitored at two locations: S1886 (Area 2) and S1870 (Area 3C).

In addition to samples collected from bores, groundwater samples are routinely collected from underground workings, inter-seam boreholes and flooded adjacent mine workings, as described in the *Underground Water Sampling and Analysis Procedure* (DENP0048). Water is analysed for chemistry (major and minor ions), and isotopes of carbon and hydrogen. Monthly water samples are taken from the main discharge points of the mine and from completed longwall panels. The results of the

sampling are reviewed each month and reported to Dams Safety NSW. More than 3,400 water samples have been collected and analysed at Dendrobium Mine since 2004 (including > 1100 tritium analyses), providing an extensive database for ongoing assessment and a basis for chemically characterising waters from various sources.

In this assessment, average field electrical conductivity (EC), is used as a general indicator of water quality (salinity). Water salinity varies according to its source (see Figure 5) and, in general, groundwater salinity tends to increase with the depth below the surface; groundwater in the HBSS tends to be relatively fresh (average EC ~ 170 μ S/cm) whereas mine seepage water is distinctly more brackish (average EC of seepage in Areas 3A and 3B ~ 2200 μ S/cm). Beneficial water use categories based on the ANZECC water quality guidelines (ANZECC, 2000) are shown for reference only. Groundwater quality is assessed further in Section 3.5.

Samples collected from bores can sometimes be influenced by drilling water, residual grout or bentonite leachate from the construction of the piezometer. Typically, this is indicated by elevated or anomalous EC, pH, sulfate, or Ca/Na ratios. Samples that show chemical evidence of influence by grout or bentonite are excluded from assessment.




Figure 5. Strip plot showing the range in EC of surface water, groundwater and mine inflow

3. ASSESSMENT OF GROUNDWATER RESPONSE TO MINING

3.1 Mine water balance

Table 2 presents mine inflow statistics (as indicated by pump-out data) for each Area for the period over which Longwall 18 was extracted (2/12/2021 to 17/5/2022). The average daily inflow to Area 3B during Longwall 18 extraction was 4.5 ML/day which represents 50% of total mine inflow for the period, slightly lower than the previous 6 longwalls (during which Area 3B accounted for 63% of total mine inflow, on average). Compared with the previous longwall, the total mine inflow increased by 11% whereas the inflow in Area 3B decreased by 14%. The increase in total mine inflow is likely due to very high rainfall during the longwall period, while the apparent decline in Area 3B inflow is due to a pause in pumping from the area in March-April 2022 (Table 2). During March-April, very high rainfall resulted in high inflows to Area 2. Pumping from Area 3B was limited to prioritise pumping from Area 2 during that time. There was a subsequent peak in pumping from Area 3B after pumping resumed in the area (following the end of Longwall 18). No anomalous inflow due to intersecting water-bearing structures such as faults or dykes was reported during the extraction of Longwall 18.

Table 2. Dendrobium Mine Inflow during the Extraction of Longwall 17 (in ML/day)

STATISTIC	AREA 1	AREA 2	AREA 3A	AREA 3B	TOTAL
<i>Longwall 18 (mean)</i>	1.01	1.86	1.70	4.48	9.06
<i>Longwall 18 (maximum)</i>	2.18	8.45	5.77	7.26	16.21
<i>Longwall 17 (mean)</i>	0.75	1.31	0.87	5.20	8.13
<i>Longwall 16 (mean)</i>	0.33	1.59	0.85	3.82	6.59
<i>Longwall 15 (mean)</i>	0.33	0.72	0.68	4.03	5.75
<i>Longwall 14 (mean)</i>	0.33	0.28	1.03	4.21	5.84

Time-series plot of total groundwater inflow to Dendrobium Mine (all mine areas) as determined from the mine water balance is shown in Figure 6 as a 30-day moving median (and 10th/90th percentiles). The total mine water balance has increased steadily from 2010 as mining progressed with peak mine inflows correlating closely with periods of high rainfall.

The mine water balances for Areas 3A and 3B are shown in Figure 7. Groundwater ingress to Area 3B increased steadily since the start of mining in that area (2013), initially correlating with the total area mined. Inflows to Area 3B plateaued and declined between 2017 and 2020, corresponding to the severe drought in south eastern Australia during that time. Since the start of 2020, the water balance for Area 3B has trended higher, correlating with the higher-than-average rainfall over the last two years. As of Longwall 12, peaks in inflow to Area 3B appear to correlate with periods of high rainfall with a lag time of between two and three months. Prior to Longwall 12, the influence of rainfall on the water balance was less distinct.

Groundwater ingress to Area 3A has declined by more than 50% as mining has progressed in Area 3B. The correlation of inflow peaks to major rainfall events in Area 3A has become less distinct since the end of Longwall 12.




Figure 6. Groundwater inflow from water balance for all mine areas (ML/day)




Figure 7. Groundwater inflow to the mine for Areas 3A and 3B (ML/d)

3.1.1 Estimates of the surface water component of mine inflow

The correlation of inflow peaks with periods of high rainfall at Area 3B implies that there is a rainfall (or surface water) induced component to mine inflow. Two approaches are used to assess the proportion of mine inflow at Area 3B that may be attributed to rainfall or surface water:

1. Baseflow separation approach, whereby the volume related to the inflow peaks is estimated as a fraction of the total inflow for a given period. Baseflow is a concept from stream flow hydrology whereby the baseflow represents the groundwater discharge component of flow, as opposed to the 'quick flow' component of rainfall runoff represented by the hydrograph peaks (in this case peaks in mine inflow following rain events).

- Isotopic tracer approach, whereby tracers of modern water (tritium and radiocarbon) are used to detect and estimate the proportion of rainfall or surface water in mine inflow samples.

The two approaches assess surface water input in different ways and will not necessarily yield similar results. The baseflow separation approach estimates the inflow component related to high rainfall events. Those events result in a rise in groundwater levels or piezometric head (within porous rock and fracture networks) which drive transient increases in mine inflow. However, the water itself may be largely derived from the release of (old) groundwater storage³ unless there are direct and rapid pathways between the surface and the goaf. This appears to be the case for Area 3B inflows and contrasts with observations at Area 2, as evidenced below.

A base-flow separation analysis of Area 3B water balance data is shown in Figure 8. The daily water balance data (grey circles) is highly variable due to the nature of pumping cycles in the underground mine and the trend is best represented as a 30-day moving average (the blue line). The moving average clearly defines peaks in net mine inflow following large rainfall events, with a two to three-month delay. Since the end of Longwall 16 there have been two major peaks in water balance at Area 3B with a third currently underway, reflecting the higher-than-average rainfall during 2020 - 2022.

Applying digital stream baseflow separation filters to the water balance data is problematic due to the high variability of the data (including negative values). Therefore, the baseflow component has been approximated by interpolating between troughs in the 30-day moving average water balance. The potential rainfall-induced inflow component is defined by the difference between the two curves (blue shading). Using this method, the rainfall-induced component of inflow has averaged ~15% since the start of Longwall 12. The apparent contribution during Longwall 18 was just 8%, but is not representative due to the limited pumping from Area 3B in March-April 2022 as described above.




Figure 8. Estimate of potential surface water component to Area 3B water balance

³ Note that the volume of groundwater storage above the longwall footprint alone is significant. Unconfined or drainable groundwater storage would be in the order of 7 GL per longwall (assuming an average longwall goaf area of 610,000 m², a Specific Yield of 3% averaged over all strata and an average saturated thickness of 370 m in Area 3B). Confined or elastic storage would be small in comparison; in the order of 20 ML (assuming a Specific Storage coefficient of around 10⁻⁶ m⁻¹; David *et al.* 2017). At the average mine inflow rate per longwall, complete drainage of the column (ignoring lateral groundwater flow) would take in the order of 20 years. Old groundwater storage release is likely to dominate mine inflow for many years.

3.1.2 Tritium in mine inflow

The modern water component in mine inflow is monitored by analysing tritium in samples collected from goaf inflow and development seepage water samples. The results are reported monthly to Dams Safety NSW. Tritium is an isotope of hydrogen (^3H), generated in the atmosphere through interactions with cosmic rays and through past atmospheric nuclear weapons testing (Clark, 2015). Tritium is incorporated into water molecules in rainfall and enters groundwater systems through recharge (rainfall and stream-bed infiltration). Tritium decays exponentially according to its half-life (12.32 years) and is typically only detectable in surface water samples and in groundwater that recharged within 4 to 5 half-lives (50 to 70 years). Detection of tritium above deep groundwater baseline levels in mine inflow samples would indicate a component of modern water in the sample (as it does for samples from Area 2).

Tritium is widely assumed to be a conservative tracer in that it is not significantly sorbed or otherwise retarded during groundwater transport (e.g. Cendón et al., 2014; Štamberg et al., 2014). However, a review by ANSTO (2018), commissioned by South32, concluded that tritium may undergo diffusive exchange with (and therefore loss to) zones of older groundwater. While the effect has not been quantified in terms of typical groundwater pathways at Dendrobium, it is important to consider when assessing tritium results. Despite possible diffusive losses, tritium remains an important and unambiguous indicator of modern water when tritium is detected above baseline levels.

A timeseries plot of tritium in groundwater samples from Area 3B goaf (at the outflow point) is shown in Figure 9. Tritium in samples collected from Area 3B goaf outflow is typically within or close to baseline concentrations in deep groundwater (represented by the shaded area below 0.2 TU in Figure 9, from (HCEO, 2022), implying that the component of modern water in mine inflow to Area 3B is very low - likely less than 9% which is the 90th percentile estimate based on binary mixing calculations. Samples are collected approximately monthly; however, analysis and reporting of results from ANSTO can take 6 to 12 months. The most recent analysis of inflow water from Area 3B is of a sample collected on 21/10/2021, 6 weeks prior to the start of Longwall 18. The latest sample contained tritium at 0.15 TU, within the range of deep groundwater.




Figure 9. Tritium concentration in water samples from Area 3B

3.1.3 Radiocarbon (¹⁴C) in mine inflow

Carbon-14 (¹⁴C) has been analysed in mine water, groundwater and surface water samples since 2020 as an additional indicator of modern water. ¹⁴C is a radioactive isotope of carbon with a half-life of 5,730 years. It is a widely used tracer for groundwater movement up to 30,000 years old. ¹⁴C is produced in the atmosphere and becomes part of the carbon cycle through uptake of plants and respiration and oxidation of the soil zone. Surface water and rainfall infiltrating into the ground contain small amounts of carbon dioxide extracted from the air. Leaving the atmosphere, the water comes in contact with the soil air, where the partial pressure of vegetation (root-respiration) generated carbon dioxide is much higher. The ¹⁴C content of these sources is the so-called “modern” level and is used for the reference in calculating the percentage modern carbon (pMC) and groundwater age. As with tritium, ¹⁴C analysis and reporting by ANSTO can several months, with lengthy delays up to 1 year due to Covid-19.

Sixteen sample results have been received from Area 3B goaf inflow since 2020. A timeseries of all sample results is shown in Figure 10. Sample location prefixes are SW = surface water, GW = groundwater (bore sample), Wk = adjacent mine workings (specifically Nebo Mine workings used for water supply). All samples collected from the Area 3B goaf outflow tank (DWS203) have low pMC ($\leq 3.1\%$) which, together with low corresponding tritium concentrations, implies that inflow to Area 3B is dominated by deep, old groundwater sources with a very small proportion of modern water. In contrast, samples from Hawkesbury Sandstone (HBSS) have a significantly higher modern carbon content.




Figure 10. Timeseries of % modern carbon in mine water samples

3.2 Deep groundwater levels – time-series hydrographs

Representative hydrographs from VWP arrays are presented and discussed below. Hydrograph plots are presented in Appendix B (Piezometric head and pressure head hydrographs).

3.2.1 Area 3B: Strata above mined longwalls

Piezometer cables in bores located above the footprint of a longwall are usually sheared or the sensors rendered inoperable by ground movements associated with mining and there is rarely a continuous record of groundwater pressures after the longwall has passed the monitoring location. Therefore, it is useful to consider groundwater monitoring data from locations above longwalls in two groups:

1. Baseline monitoring of groundwater levels as the longwall approached the monitoring location (until the cables shear). The most useful locations for this purpose are S1910, S1911, S1914, S1925, S1929, S2412, and S2192; and
2. Monitoring established over the goaf following the passage of the longwall. Currently operational locations include: S2220, S2306, S2337/S2338 and S2335A. Since 2018, new piezometer arrays were installed over previously mined longwalls 6 and 7 in Area 3A and Longwalls 12 to 18 in Area 3B.

Prior to being mined beneath:

Review of hydrographs from piezometers installed above longwalls prior to being mined beneath show evidence of depressurisation at the coal seams before mining started at Area 3A and years before mining started in Area 3B (Appendix B). Depressurisation of most overlying strata is apparent from the start of mining at Area 3A and the rate of depressurisation increased as mining moved to Area 3B, and with every successive longwall in Area 3B. Depressurisation is generally greater in the deeper formations. Transient pressure *increases* are also common as the longwall approaches or passes nearby the monitoring site and these reflect compression and relaxation of the strata as the subsidence wave passes (Booth, 2002). Recent examples are S2436 immediately after the start of Longwall 16 and S2478B towards the end of Longwall 17 (with little change during Longwall 18). Piezometer cables typically shear when the longwall passes within 10 m of the location, but at some sites shearing has occurred when the longwall was up to 660 m away (e.g. S1929).

The last observations prior to shearing at S1911 and S1914 (for example) show strong depressurisation throughout the strata, with some horizons in the CVSS at, or close to, zero pressure head. However, some sensors continue to record positive pressure heads indicating incomplete drainage of some strata or fractured rock domains above the goaf.

After being mined beneath:

Since 2018 IMC has carried out investigation drilling above extracted Longwalls 6 and 7 (Area 3A) and Longwalls 12 to 18 (Area 3B) to characterise the height of fracturing and assess groundwater conditions in strata above the longwall goaf (HGEO, 2020a, 2020b, 2021a). Eleven sites were drilled as part of the investigation, adding to five sites drilled as part of previous investigations above extracted longwalls (Longwall 9, Swamp 1b and WC21). A pre-longwall hole was drilled near the midline of Longwall 18 (hole S2521), which was then re-drilled and tested following longwall extraction. These investigations now provide a good understanding of fracturing and depressurisation above extracted longwalls at Dendrobium. The height of fracturing investigation report was reviewed by Professor Bruce Hebblewhite (2020). The main findings are summarised below:

- In both Areas 3A and 3B, mining-induced fracturing, including high-angle fracturing is highly variable but appears to extend to the surface. The density of fracturing generally decreases with height above the goaf, with anomalous fracturing within the Bald Hill Claystone and below 120 m above the goaf. On average, the density of fracturing above the 249 m wide longwalls is less than that above the 305 m wide longwalls (although the profiles are variable).
- In most over-goaf holes, fractures display a weak preferred orientation parallel to the longwall face within 100 to 200 m above the goaf, transitioning upward to lower-angle or bedding plane fractures above that height. One hole drilled above a longwall pillar shows a weak preferred orientation parallel to the longwall (length), again transitioning upward into lower-angle structures above 100-200 m.
- All holes drilled above extracted longwalls show a significant increase in horizontal permeability throughout the profile. Packer tests indicate an increase in permeability of 2 to 3 orders of magnitude relative to pre-mining conditions. At the centreline of Longwall 12 (S2420) there is an anomalous zone of apparently unaffected (near median) permeability in the upper CVSS and Bald Hill Claystone (BACS). Above the pillar zone between Longwall 11 and Longwall 12, packer tests indicate distinctly lower post-longwall permeability than the centreline holes throughout all strata.
- Changes in vertical permeability cannot be measured directly from packer testing. The decrease in high-angled fractures with height above the goaf implies that, while vertical permeability is likely enhanced throughout all strata, the ratio of vertical to horizontal permeability decreases with height above the goaf.
- VWP's installed after longwall extraction indicate significant depressurisation throughout all strata, with near-zero pressure heads recorded in most piezometers. Complete depressurisation is recorded throughout the HBSS in most holes drilled above goaf. However, holes in both areas show positive and increasing pressure heads in some sensors in the upper CVSS and BACS, indicating localised perching and recovery of groundwater levels within those strata.

In the context of previous models for fracturing above extracted longwalls, it is interpreted that the height of fracturing (and depressurisation) is highly variable but extends to the surface in Areas 3A and 3B and likely also in Areas 1 and 2. However, observations of localised perching and recovery above extracted longwalls are inconsistent with complete desaturation (draining) to the surface as predicted by Tammetta (2013). This suggests that the zone of highly connected and free-draining fracturing extends to approximately 220 to 250 m above the goaf (approximately to the base of the BACS in Area 3B).

3.2.2 Area 3B: Strata outside mined longwalls

In this section, data from piezometers located outside the current mined longwall footprint are reviewed (excluding the Avon monitoring bores which are discussed below). These include bores installed within planned mining Areas 5 and 6. Refer to hydrographs in Appendix B.

Piezometers located to the north and west, and within 1 km of the longwall footprint (S1910, S1892, S1998 / S2401, S2006 and S2007) show a gradual decline in groundwater pressures in most strata with the rate of decline increasing with depth and proximity to the longwall. Those observations are consistent with the gradual expansion of a drawdown cone away from the mine and are in line with numerical modelling predictions. The most strongly affected strata are within 500 m of extracted longwalls (S1910, S1892). At S2006 (1 km west of Longwall 9) piezometric head decreased to their lowest level in most strata towards the end of Longwall 14 and have shown recovery in within the HBSS and upper BGSS since Longwall 14.

Monitoring bores installed in Area 5 show that drawdown is minor at distances greater than 1.2 to 1.5 km from Area 3B. At S2341 (1.2 km), there is some evidence for depressurisation in the deeper sandstone strata; however, all sensors show piezometric head at an elevation corresponding to the HBSS. Similar piezometric levels are observed at S2352 (2.3 km), S2342 (2.6 km), S2345 (3.5 km) and S2340 (4.7 km). At those relatively distant locations, piezometric head within the HBSS is typically above 320 m AHD (and above the level of Lake Avon), whereas levels within the BGSS and SBSS have heads < 300 m AHD and display broadly hydrostatic profiles, with evidence for some depressurisation in deeper strata since Longwall 16. This condition has not significantly changed during the extraction of Longwall 18.

3.2.3 Avon reservoir bores

A series of monitoring bores was installed along the barrier zone between Lake Avon reservoir and Area 3B to characterise the strata permeability before and/or after mining of adjacent longwall panels and to provide ongoing groundwater monitoring. Holes are typically re-drilled and tested following extraction of the adjacent longwall(s). Those observations provide critical information to allow more accurate calculation and modelling of potential seepage losses from the reservoir(s) to the mine. Results of drilling, permeability testing and monitoring have been reported as the investigation has expanded, and hole re-drilling has been completed. A review of data was reported by HGEO (2021b) after the re-drilling of hole S2379 at site AD5 following the extraction of Longwall 17. Steep and inaccessible terrain prevented installation of further monitoring bores between Lake Avon and Longwall 18. Hydrographs for all Avon Dam series monitoring bores are included in Appendix B.

In summary, piezometers in the Lake Avon barrier zone show widespread depressurisation of all strata in response to mining in Area 3B, as predicted in numerical groundwater models (Watershed Hydrogeo, 2020). Groundwater levels at the base of the HBSS were likely near or just above the lake level prior to mining and have declined to be below the lake level. There is evidence for recovery in groundwater pressures in the CVSS at AD1, AD2, AD5, AD7, and to a lesser extent, at AD6.

The observed levels imply hydraulic gradients away from the lake and towards the mine adjacent to extracted longwalls; however, gradients remain towards the lake beyond the influence of the extracted longwalls. Perched aquifers are apparent in upper parts of the HBSS which can persist after mining.

A plot of model predicted piezometric head versus observed head at piezometers adjacent to lake Avon as of the end of Longwall 18 is shown in Figure 11. The plot shows that, for most piezometers, observed head is similar to, or higher than, the numerical model prediction. Therefore, the model predictions are generally accurate as of Longwall 18 or tend to over-estimate groundwater drawdown.




Figure 11. Modelled versus observed piezometric head for Avon Dam monitoring sites

Hydraulic gradients away from the lake imply groundwater flow from the lake to the mine and seepage loss from the lake. The rate of seepage loss is governed by the hydraulic gradient and permeability (measured and expressed as hydraulic conductivity) of the intervening strata which has been tested prior to mining (at most sites) and following extraction of longwalls. Estimates of seepage loss have been calculated using several approaches, including regional and local scale numerical models (see Section 3.4.3, below)

3.2.4 Potentially transmissive geological structures

Geological structures such as faults and fracture zones have the potential to form conduits for groundwater flow to the mine and transmit drawdown to receptors distant from the mine. The permeability structure of faults is related to the internal structure, rock type, the prevailing stress regime and post-movement mineralisation of the fault zone (Bense et al., 2013). Such factors can lead to a range of possible permeability structures, including a barrier to flow; a conduit to flow; or a complex conduit-barrier system whereby a fine-grained core may impede transverse flow and the damaged (outer) zone may promote enhanced flow along the fault. Complex barrier-window scenarios can arise where strata of varying permeability and thickness are variably off-set along the fault and fine-grained material from claystone units may be smeared along the core zone (Yielding et al., 1997).

A geological assessment, including mapped and potential structures was carried out prior to mining in Area 3B (BHP Billiton, 2013). The geology between Avon Reservoir and Area 3B mine workings was further assessed by South32 (2018) and the geology associated with Longwall 18 by South32 (2020). A combination of exploration techniques including; surface exploration boreholes, aeromagnetic and seismic surveys, surface mapping, underground in-seam drilling and underground mapping have been used to build the geological model in the area.

SRK (2020) assessed faults and surface lineaments above and around Dendrobium Mine. The assessment included analysis of mine subsidence data (LiDAR) to determine if surface subsidence is controlled by or reactivates mapped surface lineaments. The study identified several very minor linear anomalies directly above mined longwall panels in Area 3B, with none identified in Areas 2 or 3A. The

study concluded that the potential for reactivation of lineaments extending outside the planned mining areas was assessed as low.

In a separate study, HGEO (2020c) assessed of the spatial relationship between piezometric response in vibrating wire piezometers (anomalous drawdown compared with predictions) and proximity to known or inferred geological structures. The study concluded that anomalous drawdown responses are not correlated with mapped structural features. This is consistent with the observations in the underground mine that large inflows of groundwater are typically not associated with mapped linear features such as igneous dykes and faults, and with experience elsewhere in the Southern Coalfield (Doyle, 2007; Tonkin and Timms, 2015).

Notwithstanding the above, the potential for reactivation of fault zones during mine subsidence and subsequent connection with surface water bodies should not be discounted. The Elouera Fault located immediately south of Area 3B is of particular interest with respect to the extraction of Longwall 18. A detailed investigation of the Elouera fault was carried out prior to development of Longwall 18, the results of which are summarised below.

3.2.5 Elouera Fault

The Elouera Fault is located to the south of Area 3B, between Longwall 18 and Elouera Mine Longwall 8. The fault trends approximately east-west and broadly parallel to the northern tributary to Native Dog Creek (NDT1). The Elouera Fault zone is a complex fault comprising three distinct but (structurally) connected fault zones and several splay structures. The main fault plane dips to the south at between 53 and 63° (based on recent drilling) and offsets the Wongawilli Seam by up to 40 m (downfaulted to the south). The fault trace is projected to intersect the surface on the northern slopes of the NDT1 valley. Recent drilling has identified the fault within the CVSS and drilling at Swamp 35 intersected a fault zone likely associated with Elouera Fault within the lower part of the HBSS. Several lineaments trending sub-parallel to the fault are apparent in Lidar topographic data; however, the fault has not been identified in outcrop.

A hydrogeological investigation of the Elouera fault was carried out by IMC to assess the structural and hydrogeological characteristics of the Elouera Fault zone, and its potential to provide a connection between Lake Avon and the proposed longwalls. Seven inclined cored holes were drilled at three sites along the fault, four of which intersect the fault plane. Investigation holes are shown in cross sections in Figure 12; holes highlighted in green are instrumented with multi-level piezometers and, in holes that intersect the fault, Time-Domain Reflectometry cables.

Elouera Fault investigation holes




Figure 12. Cross sections of Elouera fault showing investigation holes

Preliminary results of the investigation were reported by HGEO (2020d), and are summarised below:

Elouera Fault is characterised by multiple fault cores within a broad fractured (damaged) zone that ranges between 8 m and 31 m thick (true thickness). The fault cores are planar features comprising infill of clay or pulverized rock (fault gauge or fault breccia) measuring between centimetres and several tens of centimetres thick. The fault damage zones are characterised by elevated fracture frequency compared with holes drilled outside the influence of faulting and mine subsidence.

Narrow-spaced packer testing across the Elouera Fault shows a highly variable permeability structure (and overall average permeability) between drill sites and between closely adjacent holes at the same site. The data indicate that permeable zones are discontinuous on a scale of tens of metres and the fault does not form a continuous conduit to groundwater flow. The highest average permeability was observed at the shallowest fault intersection (upper CVSS).

The BACS, a regionally important aquitard, is not completely offset and maintains continuity across the fault. The major stratigraphic units (Hawkesbury Sandstone [HBSS] and CVSS) are largely continuous across the fault with minor displacement relative to their thickness. Analysis of the effects of offsetting minor lithologies across the fault indicates that the fault likely represents a weak barrier to transverse (north-south) groundwater flow (a decrease in permeability of ~0.3 to ~0.5 orders of magnitude).

Groundwater levels observed in open holes at Site 2 and piezometers at Site 3 are above the level of Lake Avon within the HBSS and ~215 m above the water level in the adjacent Elouera Mine workings. Given that the Elouera Fault is intersected by most of the investigation holes, and is intersected by the Elouera Mine workings, these observations imply that 1) groundwater gradients within the HBSS are towards Lake Avon; 2) depressurisation of deeper strata due to previous mining at Elouera to the south and current mining in Area 3B to the north has not resulted in depressurisation of the HBSS via the fault; and 3) the fault zone is not a significant conduit to flow.

3.2.6 Elouera Fault groundwater monitoring during / post Longwall 18

This section summarises monitoring data and observations during and following extraction of Longwall 18, in relation to Elouera fault. The following data are relevant:

1. Mine inflows during Longwall 18.
2. Time-Domain Reflectometry cables installed across the fault plane.
3. Groundwater monitoring north and south of the fault, and within the fault.

Mine water inflows during Longwall 18.

As was noted in Section 3.1, no anomalous flow was associated with intersecting structures such as dykes or faults during extraction of Longwall 18.

Time-Domain Reflectometry cables installed across the fault plane

Time-Domain Reflectometry (TDR) cables are installed in two inclined boreholes that intersect the Elouera Fault, S2441B and S2465 (at investigation sites 1 and 2, respectively). The cables were installed to identify reactivation movement on the fault plane, should it occur due to subsidence associated with Longwall 18. Time-Domain Reflectometry works by sending a voltage pulse along a cable that is grouted into a monitoring bore. The pulse signal is reflected at small changes in resistance that are caused by breaks, kinks, bends or abrasions in the cable. By monitoring the reflected signals, TDR can identify and locate damage to the cable that may be caused by small ground movements such as shear on bedding or fault planes. TDR monitoring commenced on 7/12/2021 at S2441B and on 23/10/2021 at S2465 (Longwall 18 commenced on 2/12/2021). Data are compiled and reported by Geosensing Solutions (<https://geosensing.com.au/>).

As of the most recent data acquisition (30/6/2022) no anomalies have been detected at either site during Longwall 18 extraction or since its completion. It is concluded that no detectable movements have occurred on the fault plane as a result of subsidence associated with Longwall 18.

Groundwater monitoring north and south of the fault

Piezometer arrays (VWP) were installed in five monitoring holes that intersect or pass close to the Elouera fault at Sites 1, 2 and 3 (Figure 12). The piezometers were installed to monitor groundwater pressures within the fault, in strata on both sides of the fault relative to Longwall 18, and in shallow strata relative to the water level in Lake Avon. Representative hydrographs are shown in Figure 13 to Figure 15 (hydrographs for piezometers positioned within the fault core are highlighted with a red dash-dot line); all hydrographs can be found in Appendix B.

With reference to the hydrographs for Elouera Fault monitoring bores (Figure 13 to Figure 15):

- In piezometers located within the fault plane (S2441B and S2465), groundwater pressures change in unison with piezometers located in immediately adjacent strata on both sides of the fault relative to Longwall 18. There is no anomalous drawdown within the fault core, indicating that the fault is not anomalously conductive along the fault plane (which passes close to Longwall 18).
- Groundwater pressures in deeper strata show drawdown related to Area 3B, including Longwall 18 (and also previous mining at Elouera Mine immediately to the south). Drawdown is similar on both sides of the fault at the same elevation indicating that the fault is not a significant transverse barrier.
- At all three sites, there is no evidence for groundwater drawdown in shallow strata (HBSS and BACS); groundwater levels have generally increased over the course of Longwall 18, including at Site 3 (S2490) close to the projected surface trace of the fault.




Figure 13. Groundwater hydrograph for Elouera fault monitoring bore S2441B (Site 1)




Figure 14. Groundwater hydrograph for Elouera fault monitoring bore S2465 (Site 2)




Figure 15. Groundwater hydrograph for Elouera fault monitoring bore S2490 (Site 3)

3.3 Deep groundwater levels – spatial patterns

The spatial distribution of piezometric heads and drawdown in piezometric head due to mining is shown in the following figures:

1. Bores where there are one or more sensors within the HBSS that record near-zero pressure head (assumed to be desaturated; Figure 16);
2. The change (drawdown) in average piezometric head between the end of Longwall 5 (November 2009) and the end of Longwall 18 (Figure 17 to Figure 21); and
3. The piezometric head in the lower HBSS relative to the Lake Avon FSL and recent lake levels as of the end of Longwall 18 (Figure 18).

For piezometers that ceased operation within the last two years, or where there are gaps in the data, values have been extrapolated (or interpolated) as appropriate. Piezometers that have been inactive for 2 years or more are excluded from the analysis. It should be noted that calculations of drawdown since 2009 are subject to uncertainty because of the inconsistency in the depths of sensors within each geological unit between monitoring bores.

3.3.1 Spatial distribution in groundwater drawdown

Maps of observed and estimated drawdown are shown for subunits within the HBSS, BGSS (and stratigraphic equivalent within the CVSS), and the SBSS. Analysis concentrates on the Triassic sandstone formations since those units are most relevant to connected surface water processes; drawdown in the Wongawilli and Bulli coal seams is shown in time series plots (hydrographs). The coal seams, being typically more permeable than the host coal measures and overlying Narrabeen Group, depressurise well in advance of mining, defining a broad zone of drawdown around current mining areas that coalesces with residual drawdown from neighbouring historic mines.

Analysis of drawdown in the HBSS focusses on the lower 70 m of the formation (lower HBSS). Comparison of drawdown in the upper and middle parts of the formation is problematic and potentially misleading (an underestimate) because of the number of sensors within desaturated strata. The number of sensors that record zero or near-zero (< 2 m H₂O pressure head) is shown in Figure 16. It

is common for bores located above extracted longwalls to show near-zero pressure head conditions in multiple sensors implying drawdown of head below those sensors. The typical depth to water on the plateau areas prior to mining was in the order of 25 to 30 m. Therefore, sensors that are at less than 15 m depth are plotted separately (as green symbols) since it is more likely that those sensors would be desaturated under natural conditions.

Within the lower HBSS, maximum drawdown in the order of 40 to 65 m is observed in piezometer arrays above and immediately surrounding extracted longwalls. However, review of individual hydrographs (Appendix A) indicates that most strata above extracted longwalls are depressurised with evidence for perched aquifers forming above low-permeability horizons. Therefore, drawdown values above extracted longwalls should be considered as minima. Drawdown in the HBSS reduces rapidly away from the mined longwalls. Note that in some monitoring bores (e.g. S1879, S1934) pressure head values suggest there are multiple perched aquifers and therefore calculated head and drawdown values for a geological unit would be averages of those perched heads. Bores at which a groundwater increase is recorded relative to 2009 (“negative drawdown”) are shown as zero. A number of piezometers recorded groundwater recovery relative to the baseline due to the high rainfall since 2020.

Piezometric head in the lower HBSS compared with the water level in Lake Avon is shown in Figure 18. Several bores located between extracted longwalls in Area 3B and Lake Avon record piezometric heads that are below the current lake level, consistent with a gradient away from the reservoir as described previously. It should be noted that some bores contain sensors at higher stratigraphic levels that record piezometric head above the lake level (e.g. S2313_49 m) and therefore the hydraulic gradient within the barrier zone varies with both location and elevation. In addition, there is evidence for minor perched water tables persisting in some sensors. Bores at which no colour symbols are shown are those for which recent data were unavailable at the time of reporting (< 90 days before the end of the Longwall).

Observations of piezometric head in the BGSS are mainly restricted to near the extracted and planned longwalls (Figure 19 and Figure 20). Drawdown exceeding 100 m is estimated at several bores (e.g. S2486, S2510). Drawdown decreases away from the mined areas such that less than 30 m of drawdown is estimated at distances of 1.2 km or more north of Area 3B (S2341, S2006). Significant depressurisation is expected in the BGSS (and units below) due to subsidence-related fracturing extending upwards from the goaf into these units.

The SBSS (Figure 21) is depressurised in the vicinity of the mined areas. As with the BGSS, estimated drawdown decreases to the northwest with distance from Area 3B; however, depressurisation of ~77 m is observed to the northeast (S2059) due to residual drawdown from neighbouring mines.




Figure 16. Sensors recording desaturated conditions in the Hawkesbury Sandstone (2022)




Figure 17. Drawdown in piezometric head in the lower Hawkesbury Sandstone (2009-2022)




Figure 18. Piezometric head in the lower Hawkesbury Sandstone relative to Lake Avon (2022)




Figure 19. Drawdown in piezometric head in the upper Bulgo Sandstone (2009-2022)




Figure 20. Drawdown in piezometric head in the lower Bulgo Sandstone (2009-2022)




Figure 21. Drawdown in piezometric head in the Scarborough Sandstone (2009-2022)

3.4 Comparison with model predictions

3.4.1 Deep groundwater levels

In this section observed deep groundwater levels are compared with those predicted in the most recent groundwater impact model for Dendrobium Mine (Watershed Hydrogeo, 2020). The comparison was carried out by extracting the predicted heads at representative sensors as of the end of Longwall 18 from the original model output files (provided to HGEO by Watershed Hydrogeo), and plotting those heads against the observed heads (as presented in Section 3.3). It is therefore an independent assessment of the ongoing accuracy of the groundwater model predictions.

Figure 22 is a plot of the modelled and observed heads as of the end of Longwall 18. The data are coloured according to the formation, and bores that are located adjacent to Lake Avon are highlighted with concentric circles (holes, S2313, S2314, S2376, S2377, S2378, S2379, S2435, S2436, and holes S2001, S2194). Data from an accurate and well-calibrated model should cluster along the diagonal 1:1 line. Points plotting below the line indicate that observed heads are higher than predicted (i.e. the model over-predicts drawdown and is conservative), while points that plot above the line indicate that the model under-predicts drawdown at those locations.




Figure 22. Observed versus model predicted heads at the end of Longwall 18

The following are concluded from the comparison in Figure 22:

- 64% of the observed-modelled piezometric head pairs plot below the 1:1 line indicating that the model is mostly conservative with respect to predicted groundwater drawdown impacts.
- Model predictions for piezometers in the HBSS plot close to the 1:1 line, particularly those in the range 280 to 350 m head, corresponding to the elevation range for watercourses in Area 3B.

- Model and observed heads for piezometers within the HBSS adjacent to Lake Avon plot close to the 1:1 line. Observed heads within this barrier zone are therefore generally in line with model predictions.

3.4.2 Mine water balance

Figure 23 is a plot of the modelled and observed groundwater inflow to Area 3B during the extraction of Longwalls 9 to 18. The numerical model is set up with stress periods corresponding to the originally planned longwall start and end dates (approximately yearly). The plot shows that the numerical model simulates groundwater inflow to Area 3B accurately up to Longwall 13 (mid-2017). From approximately mid-2017, the model simulated groundwater inflow continues to increase in line with the cumulative area mined, whereas the mine water balance records a decline in groundwater inflow to Area 3B until 2020. From 2020, the observed mine inflow resumes an upward trend, peaking above the predicted inflow in mid-2022. The decline in observed inflow between 2017 and 2019 and the steeper increase from 2020 corresponds with record drought conditions and record high rainfall, respectively over those periods. These trends demonstrate a clear relationship between rainfall and mine inflow in Area 3B that was not apparent prior to the extreme weather events. As noted in Section 3.1, there is no clear evidence from isotopic tracers of an increase in the proportion of modern water in mine inflow since 2020.




Figure 23. Observed versus model predicted mine groundwater inflow to mine Area 3B

3.4.3 Seepage loss from Lake Avon

The actual rate of seepage loss from Lake Avon cannot be measured directly and can only be estimated by calculation (using for example, Darcy's Law) or by numerical modelling. All estimates rely on assumptions relating to the permeability and hydraulic head distribution within the sandstone barrier zone between the lake and the mine.

Forecast estimates of the net loss (seepage) from Lake Avon to of the end of Longwall 18, based on the regional groundwater model range between **0.09 and 0.45 ML/day** (Watershed Hydrogeo, 2020). This loss comprises induced leakage from, and reduced seepage to, the Lake, relative to pre-mining conditions. The estimated range is within the tolerable loss limit of 1 ML/day prescribed by Dams Safety NSW (DSC, 2014).

A local-scale numerical model was developed by HGEO (2018) to assess the effect of the observed strata permeability changes (and variability) on estimates of seepage from Lake Avon. The model was developed using MODFLOW-USG and comprised 10 layers. The hydraulic conductivity (K) of each layer was defined by interpolating the measured (post-mine) permeability from packer tests at each test bore site (Figure 24). An average post-mining hydraulic gradient was applied to produce an estimate of seepage loss per km length of lake shoreline.

The model was revised in August 2021 to include the most recent testing of strata permeability at location AD8 (S2379) following part extraction of Longwall 17 (HGEO, 2021b) (Section 3.2.3). Note that drilling of additional monitoring bores between Longwall 18 and Lake Avon was not possible due to steep and inaccessible terrain. The revised model estimated a seepage loss of 0.36 ML/day/km of shoreline. This equates to a seepage loss of **~0.89 ML/day** adjacent to Longwalls 12 to 18 (to the southern extent of the Native Dog Creek inlet). The slightly higher estimate from the local-scale model reflects the conservative assumptions used, such as uniform steady state flow towards the mine and complete desaturation above the longwall goaf.




Figure 24. Map showing the layout of the local-scale numerical model (colour shading represents variation in hydraulic conductivity)

3.5 Groundwater chemistry

Previous reviews have shown that there is no clear spatial pattern in the distribution of groundwater quality in HBSS and BGSS bores. Groundwater salinity measured using electrical conductivity (EC) for all samples collected from monitoring bores in Areas 2, 3A, 3B and 5 are summarised in Table 3. As with previous reviews, the groundwater salinity tends to increase with depth. Due to frequent catchment closures not all bores were accessed for sampling during Longwall 18. However, of the samples collected all are within 20% of the previous groundwater sample.

Two sampling pumps were identified in the last EOP report as yielding samples that has declining EC during successive longwalls: S2314_75m and S2436_35m, both bores are located between Lake

Avon and mining Area 3B. Pump S2436_90m also displays declining EC over time; however, the very high EC following installation suggests that samples may be influenced by grout or brackish water from the installation process. Further assessment has been carried out as follows:

- 2314_75m**, located between Lake Avon and Area 3B within the Hawkesbury Sandstone (Avon Dam hole AD2). A time series plot of EC and pH (Figure 25) shows that, despite the apparent decline in EC since Longwall 15, there is no clear freshening trend. The most recent sample following the end of Longwall 18 (9/6/2022) returned an EC of 130 $\mu\text{S}/\text{cm}$, similar to that reported for Longwall 17. A time series of radiogenic isotopes tritium and Carbon-14 (indicators of groundwater age) in Figure 26 shows that tritium remains very low in samples from S2314_75m with no adverse (rising) trend. Similarly, percent Modern carbon (pMC) has been consistent at $\sim 40\%$ for the last 2 years, again with no adverse trend. It is concluded that the declining EC noted in previous reports does not reflect an increase in water seepage from Lake Avon impinging on the monitoring bore site.
- S2436_35 m**, located immediately adjacent to Lake Avon within the Bulgo Sandstone (Avon dam hole AD8). Samples from this pump also show declining EC during successive longwalls since Longwall 15 (from 222 to 128 $\mu\text{S}/\text{cm}$). To date, no tritium analysis results are available for samples from this pump.




Figure 25. Time series of groundwater EC and pH at S2314_75m (AD2)




Figure 26. Time series of tritium and percent modern carbon (pMC) at S2314_75m (AD2)

Table 3. Summary of EC measurements at monitoring bores

Bore ID	Depth (m)	Unit	Area	Mean EC ($\mu\text{S}/\text{cm}$)			
				LW15	LW16	LW17	LW18
S1870	10	HBSS	Den 3A	80		67	
S1870	16.5	HBSS	Den 3A	87		74	
S1879	10	HBSS	Den 3A	75			
S1879	58	HBSS	Den 3A	233			
S1888	7.3	HBSS	Den 3A				82
S1888	10	HBSS	Den 3A	102			
S1907	10	HBSS	Den 3A		74		
S1907	23.5	HBSS	Den 3A		77		
S1934	55	HBSS	Den 3A	115			98
S1970	43	HBSS	Den 3C			86	
S2001	63	HBSS	Den 3B		183		123
S2313	54	HBSS	Den 3B			66	80
S2314	30	HBSS	Den 3B			128	
S2314	75	HBSS	Den 3B	158	144	126	130
S2321	68	HBSS	Den 5			278	
S2321	137	HBSS	Den 5			149	
S2340	65	HBSS	Den 5	386		342	
S2340	113	HBSS	Den 5			432	
S2340	137	HBSS	Den 5	2020*			
S2341	149	HBSS	Den 5			200	
S2361	70	HBSS	Den 3C			1830*	
S2365	70	HBSS	Den 3C			292	
S2376	30	HBSS	Den 3B	123			506
S2376	102	HBSS	Den 3B	193			147
S2377	34	HBSS	Den 3B		88	79	
S2377	113	HBSS	Den 3B	88	94	84	
S2378	29	HBSS	Den 3B				
S2378	89	HBSS	Den 3B	149	155	150	
S2379	47	HBSS	Den 3B	86		77	
S1879	200	BGSS	Den 3A	639			
S1907	167	BGSS	Den 3A		868		
S1970	109	BGSS	Den 3C			309	
S2313	138	BGSS	Den 3B			100	111
S2313	194	BGSS	Den 3B			512	504
S2314	128	BGSS	Den 3B	380	381	346	363
S2321	198	BGSS	Den 5			667	
S2340	215	BGSS	Den 5	129		587	
S2341	228	BGSS	Den 5			746	
S2341A	228	BGSS	Den 3C				
S2376	169	BGSS	Den 3B	396			523
S2379	128	BGSS	Den 3B	484		443	
S2436	35	BGSS	Den 3B	222	188	147	128
S2436	90	BGSS	Den 3B	4910*	480	461	436
S1870	160	SBSS	Den 3A	319		264	
S1886	22	SBSS	Den 2	486	596	497	496
S1886	30	SBSS	Den 2	524	696	571	576
S1886	38	SBSS	Den 2	621	719	585	579

Note: * Results affected by bentonite pack near pump intake. Blue shading = Average EC $\geq 20\%$ lower than previous; grey shading = declining EC trend.

4. CONCLUSION

The following conclusions are made with respect to the assessment of groundwater conditions following the completion of Longwall 18:

- The average daily inflow to Area 3B during Longwall 18 extraction was 4.5 ML/day which represents 50% of total mine inflow for the period (a similar proportion to Longwall 16). Compared with the previous longwall, the total mine inflow increased by 11% whereas the inflow in Area 3B decreased by 14%. The increase in total mine inflow is likely due to very high rainfall during the longwall period, while the apparent decline in Area 3B inflow is due to a pause in pumping from the area in March-April 2022.
- Isotopic tracers of modern water (tritium and 14C) continue to indicate negligible or minor components of modern water in water pumped from Area 3B.
- Groundwater salinity (as indicated by Electrical Conductivity – EC) shows a general increase with depth below the surface. Declining EC was reported in two monitoring bores located adjacent to Lake Avon (S2314_75m and S2436_35m) following Longwall 17. A review of water chemistry and isotopic data following Longwall 18 finds that the trend is not continuing. There is no adverse trend in isotopic indicators of groundwater age (14C and Tritium).
- Mining of Longwall 18 resulted in continued depressurisation of the target coal seam and overlying strata in general agreement with numerical model predictions. Importantly, for piezometers installed in the barrier zone between Lake Avon and Area 3B, observed head is similar to, or higher than, the numerical model prediction. Therefore, the model predictions are generally accurate as of Longwall 18 or tend to over-estimate groundwater drawdown.
- Piezometers installed after longwall extraction indicate significant depressurisation throughout all strata and throughout the Hawkesbury Sandstone (HBSS) in most holes. Holes drilled above extracted longwalls provide evidence for groundwater perching and recovery in the years following mining. Drawdown in the HBSS reduces with distance and is typically negligible at distances greater than 1.2 km from the goaf footprint.
- Piezometers installed along the barrier zone between Lake Avon and extracted longwalls in Area 3B show declines in piezometric heads to levels below contemporaneous water levels in Lake Avon and changed in strata permeability due to mine subsidence. Seepage losses from Lake Avon have been estimated by regional and local scale numerical models to be in the range 0.09 to 0.89 ML/day as at the end of Longwall 18. The estimates are within the tolerable loss limit of 1 ML/day prescribed by Dams Safety NSW and supported by the low levels of tritium and 14C in mine inflow water in Area 3B.
- The Elouera Fault is located to the south of Area 3B, between Longwall 18 and Elouera Mine Longwall 8. IMC carried out a detailed hydrogeological investigation of the fault prior to Longwall 18 which concluded that the fault was unlikely to form a conduit to flow. Subsequent monitoring confirms this to be the case. No anomalous inflow was associated with structures intersected during Longwall 18 extraction. TDR monitoring shows no evidence for movement on the fault plan during or after Longwall 18. Piezometers installed within and across the fault show no anomalous drawdown within the fault core, indicating that the fault is not anomalously conductive along the fault plane.

5. REFERENCES

- Adhikary, D.P., Poulsen, B.A., Wilkins, A., 2020. Assessment of longwall mining induced connective fracturing (No. EP201657), ACARP Report C27045. CSIRO, Australia.
- Advisian, 2016. Literature review of underground mining beneath catchments and water bodies (No. A26324), Report commissioned by WaterNSW.
- ANSTO, 2018. Tritium retardation in groundwater - A literature review (No. ANSTO-C-1533), Report by Australian Nuclear Science and Technology Organisation for South32 Ltd [Commercial in Confidence].
- ANZECC, 2000. Australian water quality guidelines for fresh and marine waters, National Water Quality Management Strategy Paper No 4. Australian and New Zealand Environment and Conservation Council, Canberra.
- Bense, V.F., Gleeson, T., Loveless, S.E., Bour, O., Scibek, J., 2013. Fault zone hydrogeology. *Earth-Sci. Rev.* 127, 171–192.
- BHP Billiton, 2015. Dendrobium Area 3B Subsidence Management Plan Volume 2: Subsidence Management Plan (Management Plan No. PDM-001-9.6.1D). South32 Illawarra Coal.
- BHP Billiton, 2013. Geology and mineral resources, Dendrobium Mine Area 3B (Report No. 201311k). BHPBilliton Illawarra Coal.
- Booth, C.J., 2002. The Effects of Longwall Coal Mining on Overlying Aquifers, in: Younger, P., Robins, N. (Eds.), *Mine Water Hydrogeology and Geochemistry*, Geological Society, London Special Publications. pp. 17–45.
- Cendón, D.I., Hankin, S.I., Williams, J.P., Van der Ley, M., Peterson, M., Hughes, C.E., Meredith, K., Graham, I.T., Hollins, S.E., Levchenko, V., Chisari, R., 2014. Groundwater residence time in a dissected and weathered sandstone plateau: Kulnura–Mangrove Mountain aquifer, NSW, Australia. *Aust. J. Earth Sci.* 61, 475–499. <https://doi.org/10.1080/08120099.2014.893628>
- Clark, I., 2015. *Groundwater geochemistry and isotopes*. CRC Press, Boca Raton, Florida, USA.
- Coffey, 2012. Groundwater study at Area 3B, Dendrobium Coal Mine: Groundwater modelling, Unpublished report for BHP Billiton Illawarra Coal.
- Contreras, I.A., Grosser, A.T., Ver Strate, R.H., 2008. The use of the fully-grouted method for piezometer installation. *Geotech. News*, BiTech Publishers Ltd.
- David, K., Timms, W., Barbour, S., Mitra, R., 2017. Tracking Changes in the Specific Storage of Overburden Rock during Longwall Coal Mining. *J. Hydrol.* 553, 304–320. <https://doi.org/10.1016/j.jhydrol.2017.07.057>
- Ditton, S., Merrick, N., 2014. A new sub-surface fracture height prediction model for longwall mines in the NSW coalfields, in: *Australian Earth Science Convention 2014, Abstracts No. 110*. Presented at the Australian Earth Science Convention, 7-10 July 2014, Geological Society of Australia, Newcastle, NSW, pp. 135–136.
- Doyle, J., 2007. A review of the permeability of geological structures in the Dendrobium Area, Report commissioned by BHP Billiton Illawarra Coal.
- DSC, 2014. Letter from the Dams Safety Committee to Illawarra Coal dated 10/03/2014 regarding Dendrobium mining within Avon Notification Area tolerable limit of risk of storage loss.
- Forster, I., 1995. Impact of underground mining on the hydrogeological regime, Central Coast, NSW, in: Sloan, S. (Ed.), . Presented at the Engineering Geology of Newcastle - Gosford Region, Australian Geomechanics Society.
- Guo, H., Adhikary, D., Gaveva, D., 2007. Hydrogeological response to longwall mining, ACARP Report C14033, CSIRO Exploration and Mining. Australian Coal Industry's Research Program (ACARP).
- Hebblewhite, B., 2020. Dendrobium Mine – Longwalls 14-18 Independent Review – Height of Depressurisation (Stage 3) (No. 1708/03.3). Report prepared for the NSW Department of Planning Industry & Environment.
- HGEO, 2022. Dendrobium Mine - Monthly report on water quality sampling for the Dams Safety NSW: July 2022 (No. D22188), Report by HGEO Pty Ltd for Illawarra Metallurgical Coal. Sydney, NSW.
- HGEO, 2021a. Effects of Longwall 17 extraction on overlying strata and groundwater conditions, Dendrobium Area 3B (No. D21158), Report by HGEO Pty Ltd for Illawarra Metallurgical Coal.

- HGEO, 2021b. Assessment of strata permeability adjacent to Avon Dam following extraction of Longwall 17, Area 3B (No. D21152), Report by HGEO Pty Ltd for South32 Illawarra Metallurgical Coal.
- HGEO, 2020a. Investigation into the height of fracturing above extracted longwalls in Area 3, Dendrobium (No. D19341), Report by HGEO Pty Ltd for Illawarra Metallurgical Coal.
- HGEO, 2020b. Effects of Longwall 16 extraction on overlying strata and groundwater conditions, Dendrobium Area 3B (No. D20374), Report by HGEO Pty Ltd for South32 Illawarra Metallurgical Coal.
- HGEO, 2020c. Spatial analysis of piezometric responses to mining, Dendrobium Areas 3A and 3B (No. D20373), Report by HGEO Pty Ltd for South32 Illawarra Metallurgical Coal.
- HGEO, 2020d. Structure and hydrogeology of the Elouera Fault (No. D20365), Report by HGEO Pty Ltd for South32 Illawarra Metallurgical Coal.
- HGEO, 2018. Review of potential seepage rates adjacent to Lake Avon, Dendrobium Area 3B (No. D18314), Memo by HGEO Pty Ltd for South32 Illawarra Coal.
- HydroSimulations, 2016. Dendrobium Area 3B Groundwater Assessment (No. HC2016/02), Report by HydroSimulations for South32 Illawarra Coal.
- IEPMC, 2019a. Independent Expert Panel for Mining in the Catchment Report: Part 1. Review of specific mining activities at the Metropolitan and Dendrobium coal mines, Report by the Independent Expert Panel for Mining in the Catchment for the NSW Department of Planning, Industry and Environment.
- IEPMC, 2019b. Independent Expert Panel for Mining in the Catchment Report: Part 2. Coal Mining Impacts in the Special Areas of the Greater Sydney Water Catchment, Report by the Independent Expert Panel for Mining in the Catchment for the NSW Department of Planning, Industry and Environment.
- McNally, G., Evans, R., 2007. Impacts of longwall mining on surface water and groundwater, Southern Coalfield, NSW, Report prepared for NSW Department of Environment and Climate Change. eWater Cooperative Research Centre, Canberra.
- Mikkelsen, P.E., Green, G.E., 2003. Piezometers in fully-grouted boreholes. Presented at the Symposium on Field Measurements in Geomechanics, Oslo, Norway.
- Mills, K.W., 2011. Developments in understanding subsidence with improved monitoring, in: Proceedings of the Eighth Triennial Conference on Management of Subsidence, 2011. Presented at the Mine Subsidence 2011, Mine Subsidence Technological Society, Pokolbin, NSW, pp. 25–41.
- Parsons Brinckerhoff, 2014. Groundwater responses to mining of Longwall 9 at area 3B, Dendrobium, Report commissioned by South32 Illawarra Coal.
- Peng, S.S., Chiang, H.S., 1984. Longwall mining. Wiley, New York.
- South32, 2020. Geology of Longwall 18 Dendrobium Area 3B, Report by Illawarra Metallurgical Coal Technical Services.
- South32, 2018. Geology between Avon Reservoir and Area 3B mine workings, Dendrobium Mine, Internal memorandum by South32 Illawarra Coal. South32 Illawarra Coal.
- South32, 2012. Dendrobium Mine Groundwater Management Plan (Management Plan No. Rev 1.5). South32 Illawarra Coal.
- SRK, 2020. Geological structures comparison investigation (No. STH055), Report by SRK Consulting for Illawarra Metallurgical Coal.
- Štamberg, K., Palágyi, Š., Videnská, K., Havlová, V., 2014. Interaction of 3H⁺ (as HTO) and 36Cl⁻ (as Na36Cl) with crushed granite and corresponding fracture infill material investigated in column experiments. J. Radioanal. Nucl. Chem. 299, 1625–1633. <https://doi.org/10.1007/s10967-013-2870-7>
- Tammetta, P., 2013. Estimation of the height of complete groundwater drainage above mined longwall panels. Groundwater 52, 826–826. <https://doi.org/10.1111/gwat.12253>
- Tonkin, C., Timms, W., 2015. Geological Structures and Fault-infill in the Southern Coalfields and Implications for Groundwater Flow. J. Res. Proj. Rev. 4, 49–58.
- Toth, J., 2009. Gravitational systems of groundwater flow: Theory, evaluation, utilization. Cambridge University Press, Cambridge, UK.
- Watershed Hydrogeo, 2020. Dendrobium Area 3B Longwall 18 groundwater assessment (No. R014i4), Report for South32 Illawarra Metallurgical Coal.
- Whittaker, B., Reddish, D., 1989. Subsidence: occurrence, prediction and control. Elsevier, Amsterdam.
- Yielding, G., Freeman, B., Needham, D.T., 1997. Quantitative fault seal prediction. Am. Assoc. Pet. Geol. Bull. 81, 897–917.

APPENDIX A: List of monitoring bores



Dendrobium groundwater monitoring bores

Bore ID	Alt_Name	MGA_mE	MGA_mN	Col_RL	Mine_Area	Sensors	First_record	Last_record	Years	%with_data
S1577	Dendrobium DDH 38	294558.0	6192446.6	376.9	Den 2	4	8/12/2004	23/09/2010	5.8	81.3
S1709	DC Elouera DDH 8	290186.4	6189934.4	434.3	Den Other	8	28/02/2005	14/06/2022	17.3	84.3
S1710	DC Elouera DDH 9	290258.0	6189645.7	432.5	Den Other	4	19/05/2005	14/06/2022	17.1	89.7
S1719	DC Dendrobium DDH 56	291202.0	6193277.0	413.6	Den 3A	1	16/06/2005	18/02/2010	4.7	91.9
S1739	DC Dendrobium DDH 62	289683.6	6191798.7	423.7	Den 3B	1	2/09/2005	19/01/2019	13.4	71.3
S1755	DC Dendrobium DDH64	289475.4	6191380.2	433.3	Den 3B	2	10/01/2006	24/04/2020	14.3	73.8
S1758	Dendrobium DDH 65	288586.6	6193106.9	408.8	Den 3B	2	26/01/2006	10/06/2014	8.4	72.1
S1800	Dendrobium DDH 70	289933.4	6193996.5	392.5	Den 3B	2	25/04/2006	31/08/2011	5.4	90.4
S1844	Dendrobium DDH 76	291391.1	6194868.8	375.6	Den 3C	2	22/08/2006	29/06/2022	15.9	69.6
S1845	Dendrobium DDH 77	291464.0	6193770.0	399.7	Den 3A	2	29/11/2006	4/01/2010	3.1	90.6
S1855	Dendrobium DDH 82	289746.5	6192833.2	366.6	Den 3B	2	11/12/2006	27/07/2016	9.6	88.8
S1867	ED Dendrobium DDH 84	293792.6	6192912.5	346.0	Den 3A	11	20/03/2007	12/07/2022	15.3	93.9
S1870	ED Dendrobium DDH 85	293593.2	6192648.2	351.5	Den 3A	12	2/02/2007	30/06/2022	15.4	89.1
S1871	ED Dendrobium DDH 86	293525.0	6193287.1	375.6	Den 3A	12	17/02/2007	30/06/2022	15.4	91.3
S1878	ED Dendrobium DDH 91	293842.3	6191994.3	337.1	Den 3A	11	24/04/2007	7/02/2020	12.8	95.2
S1879	ED Dendrobium DDH 92	291440.3	6192133.4	379.7	Den 3A	12	7/06/2007	30/06/2022	15.1	82.5
S1885	ED Dendrobium DDH 93	291504.4	6192667.9	420.0	Den 3A	12	7/06/2007	17/05/2012	4.9	91
S1886	ED Dendrobium PDH 94	295883.8	6191719.6	307.5	Den 2	1	23/03/2007	15/06/2022	15.2	89.5
S1888	ED Dendrobium DDH 96	292486.5	6191987.4	381.3	Den 3A	8	31/05/2007	30/06/2022	15.1	73.1
S1889	ED Dendrobium DDH 97	292244.8	6192980.4	435.4	Den 3A	8	2/06/2007	10/08/2011	4.2	92
S1890	ED Dendrobium DDH 98	292637.3	6192490.5	407.1	Den 3A	8	31/07/2007	7/08/2012	5	100
S1892	ED Dendrobium DDH 99	291014.1	6193952.0	356.1	Den 3A	8	7/08/2008	4/04/2022	13.7	47.3
S1902	ED Dendrobium DDH 100	295241.3	6190779.8	343.1	Den 2	4	4/10/2007	15/06/2022	14.7	87.1
S1907	ED Dendrobium DDH 103	293212.2	6191943.1	371.9	Den 3A	8	25/01/2008	30/06/2022	14.4	89.1
S1908	ED Dendrobium DDH 104	288925.9	6193601.4	405.7	Den 3B	8	16/05/2008	1/05/2014	6	79.7
S1910	EDEN105	289387.4	6194176.3	377.2	Den 3B	8	29/08/2008	5/03/2019	10.5	76.5
S1911	EDEN106	288802.8	6192549.4	405.2	Den 3B	12	15/05/2008	24/05/2017	9	96.7
S1914	EDEN107	289370.0	6192511.9	414.5	Den 3B	7	29/04/2008	10/08/2017	9.3	79.4
S1925	ED Dendrobium DDH 108	289251.6	6193041.1	416.7	Den 3B	8	4/08/2008	30/06/2022	13.9	88.4
S1926	ED Dendrobium DDH 109	289660.4	6193444.9	409.0	Den 3B	8	27/08/2008	8/08/2014	5.9	96.3
S1927	ED Dendrobium DDH 110	290066.0	6192211.0	414.8	Den 3B	8	16/05/2008	23/01/2017	8.7	88.9
S1929	ED Dendrobium DDH 111	290010.6	6193398.1	337.7	Den 3B	8	27/08/2008	8/08/2014	5.9	97
S1930	ED Dendrobium DDH 112	290367.3	6193582.9	353.1	Den 3B	12	27/05/2008	10/06/2021	13	83
S1931	ED Dendrobium DDH 113	290335.6	6192889.9	396.4	Den 3B	9	11/08/2008	30/06/2022	13.9	78.5
S1932	ED Dendrobium DDH 114	288863.3	6191505.4	396.1	Den 3B	11	31/08/2008	10/03/2020	11.5	89.8
S1934	ED Dendrobium DDH 115	292128.0	6192398.0	427.5	Den 3A	4	5/12/2009	22/12/2021	12	63.1
S1969	EDEN118	293998.1	6193985.7	368.5	Den 3C	11	12/08/2009	5/05/2021	11.7	59.2
S1992	EDEN119	293732.1	6192706.8	339.1	Den 3A	8	10/05/2009	30/06/2022	13.1	94.7
S1994	EDEN120	293865.2	6192982.4	345.5	Den 3A	8	13/01/2009	30/06/2022	13.5	66.6
S1995	EDEN121	288212.4	6193662.3	404.5	Den 3B	2	12/06/2009	28/01/2014	4.6	65.6
S1998	EDEN122	287750.6	6194273.1	410.5	Den 3B	2	11/06/2009	15/01/2020	10.6	63.5
S1999	EDEN123	289232.8	6190843.7	406.4	Den 3B	2	10/07/2009	20/04/2021	11.8	83.9
S2000	EDEN124	290161.4	6191011.2	442.0	Den 3B	2	10/07/2009	9/06/2021	11.9	74.4
S2001	EDEN125	288462.6	6192020.0	413.9	Den 3B	10	6/08/2009	1/07/2022	12.9	96.4
S2002	EDEN126	288633.4	6194222.1	400.0	Den 3B	2	21/07/2009	19/02/2012	2.6	85.3
S2003	EDEN127	290571.1	6192478.0	409.4	Den 3B	2	4/08/2009	1/03/2014	4.6	10.8
S2006	EDEN129	287263.2	6194204.3	409.1	Den 3B	10	24/07/2009	30/06/2022	12.9	75.4
S2007	EDEN130	287590.8	6193718.9	405.8	Den 3B	2	17/06/2009	16/06/2022	13	69.1
S2009	EDEN131	287828.2	6193092.0	402.5	Den 3B	10	10/08/2009	24/03/2016	6.6	24.1
S2013	EDEN134	290857.7	6191198.2	399.7	Den 3B	2	22/07/2009	16/06/2022	12.9	69
S2059	EDEN148	293245.7	6194795.1	380.8	Den 3C	11	16/08/2011	30/06/2022	10.9	61.5
S2070	EDEN150	287619.3	6192813.2	414.7	Den 3B	2	15/05/2013	14/06/2022	9.1	80
S2078	EDEN154	288190.0	6192451.9	342.0	Den 3B	2	20/06/2010	13/03/2017	6.7	96.7
S2192	S2192	289826.7	6193848.7	389.3	Den 3B	6	25/03/2013	18/11/2014	1.7	34.8
S2194	S2194	288514.9	6190978.8	371.1	Den 3B	11	13/04/2013	1/04/2018	5	98.8
S2208	S2208	292801.1	6195037.3	344.0	Den 3C	8	19/12/2014	31/10/2020	5.9	99.8
S2211	S2211	293247.0	6194106.0	397.7	Den 3C	2	2/10/2013	1/07/2022	8.7	94
S2212	S2212	293534.8	6194402.9	369.2	Den 3C	10	11/10/2013	30/06/2022	8.7	98.5
S2220	S2220 (AQ5)	289827.2	6193830.7	388.1	Den 3B	3	12/11/2014	30/06/2022	7.6	99.9
S2306	Swamp Bore 3 (adjacent)	288643.3	6192483.7	395.5	Den 3B	4	16/09/2015	19/06/2022	6.8	95.1
S2307	Swamp Bore 4	288665.9	6192424.6	394.5	Den 3B	4	16/09/2015	19/06/2022	6.8	95.6
S2309	Dendrobium S2309_R	287689.9	6194933.2	412.0	Den 3D	10	15/07/2015	30/06/2022	7	97.2
S2312	Dendrobium S2312	284450.1	6196150.7	409.4	Den 3D	10	12/08/2015	18/06/2022	6.9	84
S2313	Avon 1	287609.0	6192815.5	415.3	Den 3B	3	31/10/2015	30/06/2022	6.7	93.1
S2314	Avon 2	288193.5	6192470.3	342.4	Den 3B	3	13/11/2015	30/06/2022	6.6	94.3
S2321	Dend S2321	284710.0	6195575.5	411.0	Den 3D	2	12/08/2016	30/06/2022	5.9	98.5
S2325	Dend S2325	283596.2	6195466.7	433.5	Den 3D	8	6/09/2016	30/06/2022	5.8	96


Dendrobium groundwater monitoring bores

Bore ID	Alt_Name	MGA_mE	MGA_mN	Col_RL	Mine_Area	Sensors	First_record	Last_record	Years	%with_data
S2333	Dend s2333 (D-A3C-14-12)	290697.1	6197087.4	310.9	Den 3C	10	8/10/2016	30/06/2022	5.7	97.2
S2335	WC21Project Hole1Site 2	289725.4	6192748.7	372.6	Den 3B	5	19/10/2016	12/11/2016	0.1	96
S2336	WC21Hole2,Site2	289721.9	6192758.1	372.4	Den 3B	2	21/10/2016	20/07/2017	0.7	81.3
S2337	WC21Project Hole1Site 5	290021.0	6193411.9	336.1	Den 3B	3	25/11/2016	30/06/2022	5.6	93.4
S2338	WC21Hole2,Site5	290012.2	6193406.7	336.1	Den 3B	3	24/11/2016	30/06/2022	5.6	93.4
S2340	D-A5-25	285468.1	6197978.9	396.9	Den 3D	9	7/12/2016	30/06/2022	5.6	92.4
S2341	D-A5-28	287473.5	6195149.8	401.6	Den 3D	10	7/12/2016	30/06/2022	5.6	99.9
S2341A	D-A5-28A	287489.0	6195138.2	402.6	Den 3C	4	21/12/2016	30/06/2022	5.5	95.9
S2342	D-A5-12	287953.2	6196755.8	403.2	Den 3D	10	23/12/2016	30/06/2022	5.5	98.4
S2345	D-A5-19	285356.8	6196094.9	402.0	Den 3D	12	29/04/2017	30/06/2022	5.2	93.9
S2348	D-A5-17	286450.5	6196461.9	396.3	Den 3D	13	11/08/2017	30/06/2022	4.9	66.7
S2351	S14-04	290049.6	6191178.2	402.8	Den 3B	2	1/09/2017	1/07/2022	4.8	81.4
S2352	D-A5-6	286264.6	6195393.3	408.8	Den 3C	10	27/04/2017	25/05/2022	5.1	78.4
S2354	S14_05	289730.9	6191413.7	424.6	Den 3B	1	7/09/2017	30/06/2022	4.8	95.2
S2355	A5_S85_DBH	288136.2	6194877.8	396.6	Den 3C	5	5/08/2017	18/06/2021	3.9	100
S2357	A5-S100_DBH	286809.6	6196991.8	394.0	Den 3C	4	29/07/2017	13/03/2021	3.6	89.7
S2359	D-A5-5	285354.6	6195547.7	403.6	Den 3C	10	11/08/2017	30/06/2022	4.9	66.6
S2361	A5_S109_DBH	286277.9	6195810.7	402.4	Den 3C	4	24/06/2017	25/07/2022	5.1	73.4
S2362	A5_S110_DBH	285772.9	6195823.0	399.9	Den 3C	4	23/06/2017	18/06/2021	4	83.9
S2364	A5_S103_DBH	285982.8	6196782.1	395.0	Den 3C	4	14/11/2017	18/06/2021	3.6	68.4
S2365	A5_101/102_DBH	286042.3	6196448.9	399.2	Den 3C	5	4/09/2017	18/06/2021	3.8	100
S2366	A6_S113_DBH	291865.1	6200199.1	358.6	Den 3D	4	23/05/2018	16/07/2021	3.2	100
S2367	A6_S117_DBH	291630.7	6199726.5	356.1	Den 3D	4	23/05/2018	16/07/2021	3.2	100
S2370	D-A5-2	285554.8	6196642.7	375.6	Den 3C	10	12/05/2018	18/09/2020	2.4	61.2
S2371	A6_S116_DBH	291977.5	6199135.2	351.2	Den 3C	4	23/05/2018	16/07/2021	3.2	100
S2372	A6_S115_DBH	291576.9	6198891.4	373.5	Den 3C	4	23/05/2018	16/07/2021	3.2	100
S2373	A6_S112_DBH	292043.2	6200899.2	359.0	Den 3C	4	7/10/2017	16/07/2021	3.8	100
S2374	A6_S83_DBH	291114.8	6201461.1	324.4	Den 3C	4	24/05/2018	16/07/2021	3.1	100
S2376	Avon 6	288400.4	6192527.0	367.8	Den 3B	3	6/10/2017	15/06/2021	3.7	100
S2377	Avon 3	288333.4	6192020.4	408.2	Den 3B	3	2/06/2018	1/07/2022	4.1	97.9
S2378	Avon 4	288407.4	6191770.9	379.3	Den 3B	4	15/11/2017	15/06/2021	3.6	76.9
S2379	Avon 5	288312.9	6191140.5	356.6	Den 3B	3	17/07/2018	7/12/2021	3.4	46.5
S2398	LW14_1	289073.2	6192164.3	420.2	Den 3B	8	11/05/2018	15/08/2018	0.3	100
S2398B	LW14-1 post extraction Redrill	289070.9	6192172.6	418.0	Den 3B	8	8/03/2019	31/07/2021	2.4	99.2
S2399	LW12_1	289810.5	6192965.1	355.1	Den 3B	8	3/05/2018	30/06/2022	4.2	67.8
S2401	Den01b_R1	287752.2	6194264.9	411.1	Den 3B	6	16/11/2018	24/07/2022	3.7	80.5
S2402	Den01b_R2	288207.8	6193666.6	403.4	Den 3B	6	6/07/2018	25/07/2022	4.1	80.5
S2403	Den01b_R3	288345.1	6193761.1	400.7	Den 3B	6	16/11/2018	25/07/2022	3.7	82.6
S2404	Den01b_R4	288528.6	6193896.8	396.2	Den 3B	6	22/11/2018	25/07/2022	3.7	82.3
S2405	Den01b_R5	288729.5	6194087.6	386.1	Den 3B	6	17/11/2018	25/07/2022	3.7	82.5
S2406	Den01b_R6	288669.1	6194176.5	396.6	Den 3B	6	17/11/2018	25/07/2022	3.7	82
S2408	GW14-2	289552.1	6192193.4	398.1	Den 3B	7	3/10/2018	30/06/2022	3.7	86.4
S2409	GW14-3	289546.1	6192269.7	394.6	Den 3B	6	3/10/2018	30/06/2022	3.7	92.9
S2411	LW12_2	289761.1	6192837.7	364.0	Den 3B	8	5/07/2018	30/06/2022	4	99.4
S2412	GW15-1	289201.1	6191807.4	427.3	Den 3B	8	12/05/2018	17/06/2019	1.1	97
S2412B	GW15-1	289201.6	6191803.7	425.2	Den 3B	8	18/12/2019	30/06/2022	2.5	99.1
S2420	LW12-3	289738.4	6192780.0	367.8	Den 3B	8	3/10/2018	30/06/2022	3.7	88.5
S2421	LW13-1	289590.4	6192492.2	381.8	Den 3B	8	8/02/2019	30/06/2022	3.4	80.9
S2435	AD7	288080.8	6192411.6	328.2	Den 3B	3	21/11/2018	30/06/2022	3.6	100
S2436	AD8	288313.8	6191499.7	320.3	Den 3B	5	4/12/2018	30/04/2022	3.4	97.3
S2438		287944.9	6197535.1	399.3	Den 3C	9	23/11/2018	30/06/2022	3.6	100
S2442A	S2442A-SandyCreek	292788.5	6193213.2	407.6	Den 3A	6	14/03/2019	23/02/2022	3	95.8
S2443	Sandy Creek series	292176.0	6193027.4	426.7	Den 3A	6	3/08/2019	28/06/2022	2.9	88.2
S2478B	Waterfall 54 A3B-03	290617.6	6190486.1	380.1	Den 3B	4	4/06/2020	30/06/2022	2.1	99.7
S2486	GW-12-4	288902.8	6192710.7	412.1	Den 3B	7	18/12/2019	30/06/2022	2.5	97.9
S2487	GW15-2	290707.0	6191689.0	435.3	Den 3B	5	28/11/2019	1/07/2022	2.6	76.6
S2490	Swamp 35B	289178.0	6190358.0	347.6	Den 3B	4	31/01/2020	14/06/2022	2.4	91
S2493	LW17_1	289659.3	6191107.3	434.8	Den 3B	9	2/04/2020	9/04/2021	1	100
S2493B	GW17-1	289658.0	6191102.0	435.3	Den 3B	9	10/10/2021	30/06/2022	0.7	100
S2498	S17-18 (Shaft)	287945.1	6195166.6	406.7	Den 5	8	6/06/2020	30/06/2022	2.1	98.1


APPENDIX B: Groundwater hydrographs




S1709




S1709




S1710




S1710




S1719




S1719




S1739




S1739




S1755




S1755




S1758




S1758





S1800




S1800







S1845




S1845




S1855




S1855




S1867




S1867





S1870




S1870








S1878




S1878







S1885




S1885




S1886




S1886




S1888




S1888




S1889




S1889




S1890




S1890




S1892




S1892




S1902




S1902




S1907




S1907





S1908




S1908







S1911




S1911




S1914




S1914




S1925




S1925




S1926




S1926




S1927




S1927




S1929




S1929




S1930




S1930




S1931




S1931




S1932




S1932




S1934




S1934




S1969




S1969




S1992




S1992




S1994




S1994




S1995




S1995




S1998




S1998




S1999




S1999




S2000




S2000




S2001




S2001




S2002




S2002




S2003




S2003




S2006




S2006




S2007




S2007




S2009




S2009





S2013




S2013







S2070




S2070





S2078




S2078







S2194




S2194




S2208




S2208




S2211




S2211




S2212




S2212




S2220




S2220




S2306




S2306




S2307




S2307




S2309




S2309




S2312




S2312




S2313




S2313




S2314




S2314





S2321




S2321







S2333



S2333




S2335




S2335




S2336




S2336




S2337




S2337




S2338




S2338




S2340




S2340




S2341




S2341




S2341A




S2341A




S2342




S2342





S2345




S2345







S2351




S2351




S2352




S2352





S2354




S2354








S2357




S2357










S2361




S2361










S2365




S2365








S2367




S2367







S2371




S2371




S2372




S2372




S2373




S2373




S2374




S2374







S2376





S2376













S2398B




S2398B







S2401




S2401




S2402




S2402




S2403




S2403




S2404




S2404





S2405




S2405







S2408




S2408







S2409





S2409















S2420




S2420









S2435




S2435




S2436




S2436




S2438




S2438




S2441




S2441




S2441B




S2441B







S2442A




S2442A









S2478B




S2478B





S2486




S2486







S2490




S2490




S2493




S2493




S2493B




S2493B




S2498




S2498




S2503




S2503





S2504




S2504








S2508A




S2508A










S2511




S2511









S2526



S2526



S2545



S2545

